BRAYMAN CONSTRUCTION INC.
411 St. John Street, Merrickville, ON K0G 1N0

CUSTOMER-FACING ESTIMATE

QUOTED PRICE

Client	Linda Bushel	**Project**	Bushel Rear Deck (pool deck)
Site	12 D'Arcy's Way, Kemptville, ON K0G 1J0	**Date**	2026-10-27

$30,179.51 + HST

Total including HST: $34,102.85

Brayman Construction Inc. proposes to supply and complete the scope described below based on the reviewed construction drawings and agreed final build scope.

Included Scope	Description
Helical pile foundation	Galvanized steel helical piles with adjustable brackets, supplied and installed by a specialist foundation contractor; engineer's report and compliance letter if the town asks for it. No concrete footings.
Structural framing	Pressure-treated built-up 2×10 beams, 2×8 joists and 6×6 posts, with galvanized connectors, hangers, bolts and structural screws. Freestanding; not attached to the pool.
Upper deck	About 18 ft wide, with the inner edge following the curve of the pool and about 5 ft of clear deck at the centre.
Stairs	10 ft wide, pressure-treated 2×12 stringers, Trex Island Mist treads and risers.
Lower deck	10 ft wide by 3 ft deep.
Composite decking	Trex Select composite decking in Island Mist on the upper deck, the lower deck and the stairs, with Trex deck fasteners.
Fascia	Trex Island Mist fascia on the exposed edges, with colour-matched screws.
Railing and gate	Vista 42 in aluminium railing, textured black, standard pickets, on the upper deck sides and front, both sides of the stairs and the lower deck; matching 42 in high, 48 in wide gate centred on the lower deck.
Installation	Complete installation by Brayman Construction, including clean-up of construction debris.

Price

Price Component	Amount
Estimate subtotal	$30,179.51
HST 13%	$3,923.34
Total including HST	$34,102.85

BRAYMAN CONSTRUCTION INC.
411 St. John Street, Merrickville, ON K0G 1N0

Exclusions / Separate Work

- **Town building-permit fee (Brayman can apply for the permit; the town's fee is billed at cost).**
- **Electrical work.**
- **Plumbing and HVAC work.**
- **Painting and decorative finishes.**
- **Site grading, landscaping and drainage work.**
- **A guard along the open pool edge, and skirting under either deck.**
- **Pile extensions, if the foundation contractor must go deeper to reach the required resistance (agreed with you first).**
- **Owner to provide about 46 in of access for the pile machine and to point out private buried services.**
- **Owner-requested changes, concealed conditions and revisions to drawings/engineering after acceptance.**
- **This estimate is valid for 7 days; supplier prices are time-limited.**
- Project-specific inclusions are listed in the included-scope table.