BRAYMAN CONSTRUCTION INC.
411 St. John Street, Merrickville, ON K0G 1N0
CONFIDENTIAL - INTERNAL ESTIMATING

LABOUR CALCULATION DETAIL

INTERNAL ONLY

Client	Linda Bushel	**Project**	Bushel Rear Deck (pool deck)
Site	12 D'Arcy's Way, Kemptville, ON K0G 1J0	**Date**	2026-10-27

Direct labour hours, rates, and quoted totals are project-specific and are not stored in this reusable master.

Labour Task	Basis / Scope	Hours	Direct labour	GM reference sell
Layout and mark the pile locations	deck and stair lines; 11 pile locations marked for Pro Post (Pro Post supplies AND installs the piles: no pile labour here)	4	$300.00	$352.94
Posts and beams	11 posts cut on brackets; built-up 2×10 beams (7 × 12 ft + 4 × 10 ft), 3/8 in carriage bolts	16	$1,200.00	$1,411.76
Upper-deck framing	16 joists cut to the pool curve, 8-piece curved header with 14 skewed hangers, blocking	24	$1,800.00	$2,117.65
Lower-deck framing	9 joists 3 ft, lower beam, blocking, lower posts cut on site	8	$600.00	$705.88
Stairs	10 ft wide, 4 treads, 5 risers; stringers cut and hung	16	$1,200.00	$1,411.76
Trex decking	about 147 sq ft (upper 116.8 + lower 30), every board scribed to the pool curve on the upper deck	16	$1,200.00	$1,411.76
Stair treads and risers (Trex)	8 tread boards, 5 riser boards 10 ft	8	$600.00	$705.88
Trex fascia	about 44 ft of exposed rim, colour-matched screws	5	$375.00	$441.18
Railing blocking	solid blocking under each Vista post base	4	$300.00	$352.94
Vista railing and gate	11 sections, 14 posts on base plates, pickets, 48 in gate	16	$1,200.00	$1,411.76
Unload and carry materials	BMR delivery to the back yard (carrying is extra from BMR)	4	$300.00	$352.94
Clean-up and final walk-through	debris, offcuts, punch list	4	$300.00	$352.94
Total	Two-person crew	125	$9,375.00	$11,029.41

Labour Control

Metric	Amount
Total man-hours	125
Direct labour rate	$75.00 per man-hour (Brayman rate from 27 Oct 2026)
Direct labour	$9,375.00
GM reference sell (15% true gross margin)	$11,029.41
Crew and duration	Two-person crew, about 7.8 working days
Helical piles	Supplied and installed by Pro Post Foundations (OT-2236); no pile installation in Brayman labour
Basis	Joel's estimating allowance (27 Oct 2026) from the J1 take-off and supplier quantities
For Ben	Review each line; adjust the hours of any task from your experience and the price is recalculated

Direct labour hours and rates are project-specific and are not stored in this reusable master.