Linda Bushel — preliminary estimate

Date: 2026-10-01

PRELIMINARY / BUDGET ESTIMATE

Subject to permit review and a check on site.

Selling price: NOT ISSUED.

No supplier price has come back. This sheet does not state a dollar figure.

Project

Linda Bushel. Freestanding pressure-treated deck and stairs at an above-ground pool.

12 D'Arcy's Way, Kemptville, ON K0G 1J0.

The drawing in this package is a preliminary construction and pricing set. It is not a final construction drawing, not an engineering approval, not a town approval, and not a structural certification.

Scope

• Above-ground pool about 21 ft in diameter and about 50 in high. Check on site.

• Upper deck 18 ft wide. The pool edge is curved and left open. The other three edges are straight. 5 ft clear at the centre.

• Framing: one straight main beam and two wing beams.

• 15 helical piers at the drawn locations. No sonotubes and no concrete. Shaft, helix, length, and capacity are not chosen.

• 16 joist lines. 2×8 joists. Curved header in straight pieces.

• Stairs 10 ft wide, about 38 in between the two decks, five risers about 7.6 in, four treads about 11 in. The upper deck is the top landing.

• 10 stair stringers. Each tread is two 5/4×6 boards.

• Stringer throat 5.00 in. That figure is a working size for this preliminary set. It is not an engineering certification.

• Lower deck 10 ft by 3 ft. Walking surface 12 in above grade.

• Guard: the named 37 in Veranda rail kit. Gate 42 in clear, swings out, self-closing and self-latching.

• 1×6 skirt on the lower deck only, fitted tight.

• Freestanding. No attachment to the pool.

Assumptions

• Brown pressure-treated lumber.

• Joist spacing is 16 in on centre maximum, with a 4 in space at each upper outside edge.

• Stringer spacing uses the same 4 in edge spaces. Ten stringers.

• Waste is the leftover on the stated stock lengths. No extra percentage is added.

• The lower 6×6 posts are ordered uncut. Cut them on site. Beam, joist, and decking dress out at 17.5 in.

• Pool-enclosure compliance, including the 1.2 m rule, stays with the site and the town. The 37 in kit is not redrawn to another height.

Exclusions

• Engineering seal and structural certification.

• Town permit and permit fees.

• Attachment to the pool.

• A centre handrail on the stairs.

• A guard along the curved pool edge.

- Upper-deck skirting.
- A selling price, deposit, or start date.

Check on site

Pool size and height, finished grades, setbacks, property limits, helical pier product, depth, torque, and bearing, stair rise and run after both deck surfaces are measured, lower-deck post cut, and pool-enclosure height.

Supplier

The request to BMR Winchester is ready to send. It has not been sent, and no price has come back. The helical pier product, bracket, rail match, gate hinge count, connector brands, bolt diameter, availability, substitution, and delivery timing stay open. The supplier confirms those items. They are not filled in on this estimate.