Brayman Construction
Brayman Construction Inc.
411 St. John Street, Merrickville, Ontario K0G 1N0

ITEMS THAT NEED A COST

For Ben. Type in the boxes and send this PDF back.

Linda Bushel — items that need a cost. For Ben only. Not a customer document.

Quantities are the 1 Oct 2026 preliminary issue: 15 helical piers, 16 joist lines, 10 stringers. No sonotubes and no concrete. The walking surface and the stair treads are Trex. Fascia is added on the exposed rim.

Type in the boxes. Save this PDF and send it back. A blank is not zero. No price on this sheet was filled in for you.

No extra waste percentage is added. Leftover length stays on the cut lists and is not deducted from these quantities.

No.	Item	Qty	Unit price	Line price	Note
1	Helical pier. Shaft, helix, length, torque, and capacity are not chosen.	15			
2	Helical-pier bracket, unless the pier price includes it.	15			
3	PT 6×6 × 8 ft. Lower posts are ordered uncut.	11			
4	Post-to-beam connector. Brand is not chosen.	15			
5	PT 2×10 × 10 ft	4			
6	PT 2×10 × 12 ft	7			
7	PT 2×8 × 12 ft	20			
8	PT 2×12 × 8 ft stringer stock	10			
9	Trex composite deck board × 20 ft. Upper deck, cut to 18 ft. One row ripped to 5 in width. Colour and product line are not chosen.	11			
10	Trex composite deck board × 10 ft. Lower deck, stair treads, and pieces beside the pool. Colour and product line are not chosen. Say if this length is not sold.	17			
11	Trex composite deck board × 8 ft. Shorter pieces beside the pool. Colour and product line are not chosen. Say if this length is not sold.	7			
12	Trex fascia. Upper sides 10.092 ft each, upper front returns 4 ft each, lower sides 3 ft each, lower front 10 ft. The open pool edge has no fascia. The stair stringer faces have no fascia. Colour, width, and stock length are not chosen.	44.184 ft			
13	PT 1×6 × 8 ft skirt	5			
14	Veranda 37 in × 6 ft, matching the named look. The Home Depot number is not a confirmed BMR item.	10 kits			
15	Custom stair guards. These are not a 6 ft kit.	2			
16	PT 4×4 × 8 ft guard posts	14			
17	Gate, 42 in clear	1			
18	Gate latch, and hinges. Latch count is 1. Hinge count is not stated.	Latch 1			
19	Stitch bolts, nuts, and washers. 76 bolts, 76 nuts, 152 washers. Diameter is not chosen. Count is for pricing, not an engineered layout.	76 / 76 / 152			
20	Header connectors. Brand is not chosen.	16			

Brayman Construction
Brayman Construction Inc.
411 St. John Street, Merrickville, Ontario K0G 1N0

ITEMS THAT NEED A COST

For Ben. Type in the boxes and send this PDF back.

No.	Item	Qty	Unit price	Line price	Note
21	Stringer connectors. Brand is not chosen.	10			
22	Structural screws	100			
23	Fasteners for the Trex boards. The count is two fasteners at each board crossing. The Trex fastener is not chosen.	798			
24	Labour for this deck. No hours are on file. State the hours and the rate, or one labour amount.				
25	Equipment. None is listed. Name each item and its cost, or write none.				
26	Delivery to 12 D'Arcy's Way, Kemptville, ON K0G 1J0				
27	Disposal				
28	Permit fees. The customer estimate excludes them. Say whether Brayman pays them.				

Priced by

Date