BMR Winchester request for a price — Linda Bushel

Preliminary Construction and Supplier Pricing Basis - Subject to Permit Review and Field Verification

Date: 2026-10-01

Prepared for Darcy at BMR Winchester. This is a request for a price. It is not a quotation. It has not been sent.

Project

Field	Value
Client	Linda Bushel
Delivery site	12 D'Arcy's Way, Kemptville, ON K0G 1J0
Contractor	Brayman Construction Inc., 411 St. John Street, Merrickville, ON K0G 1N0
Drawing and take-off	In this package

Brown pressure-treated lumber. Freestanding deck. No attachment to the pool.

A website price, if one is compared later, is a guide only.

No BMR price has been confirmed, so the price columns are blank.

A blank SKU, price, availability, substitution, or delivery cell means please confirm it.

A blank is not zero, and it is not a quotation.

Request lines

Group	Description	Preferred stock	Qty	Unit	BMR SKU	Public price	Contractor price	Availability	Substitution	Delivery timing	Flag
Piers	Helical pier, one at each drawn location	product not chosen	15	ea							Please confirm shaft, helix, length, and torque. Not a sonotube. No concrete.
Piers	Helical pier post bracket	each	15	ea							Please confirm, unless the pier already includes the bracket.
Posts	PT 6×6 × 8 ft	8 ft	11	ea							5 sticks for 9 upper posts. 6 sticks uncut for the lower posts.

Group	Description	Preferred stock	Qty	Unit	BMR SKU	Public price	Contractor price	Availability	Substitution	Delivery timing	Flag
Posts	Post-to-beam connector, PT compatible	each	15	ea							Please confirm the product.
Beams	PT 2×10 × 10 ft	10 ft	4	ea							Lower beams used full length.
Beams	PT 2×10 × 12 ft	12 ft	7	ea							Front pieces cut to 6 ft. Main beam used full. Wings cut to 5.41 ft.
Joists	PT 2×8 × 12 ft	12 ft	20	ea							Joists, header, blocking, and lower joists.
Stairs	PT 2×12 × 8 ft stringer stock	8 ft	10	ea							Stock only. Not a finished stringer.
Decking	PT 5/4×6 × 20 ft	20 ft	11	ea							Cut to 18 ft. One row ripped to 5 in width.
Decking	PT 5/4×6 × 10 ft	10 ft	17	ea							Lower deck, treads, and pieces beside the pool.
Decking	PT 5/4×6 × 8 ft	8 ft	7	ea							Shorter pieces beside the pool.
Skirt	PT 1×6 × 8 ft	8 ft	5	ea							Lower deck only. Tight fit. Cut to 12 in.
Rails	Veranda 37 in × 6 ft kit, look of HDDR2022005, SKU 1001900458	6 ft	10	ea							Home Depot number. Not confirmed as a BMR item.
Rails	PT 4×4 × 8 ft guard posts	8 ft	14	ea							Please confirm the kit does not already include posts.

Group	Description	Preferred stock	Qty	Unit	BMR SKU	Public price	Contractor price	Availability	Substitution	Delivery timing	Flag
Gate	42 in clear self-closing, self-latching gate to match the rail	custom	1	ea							Hinge count not stated.
Fasteners	PT-compatible stitch bolts, nuts, washers	diameter not chosen	76 bolts / 76 nuts / 152 washers	ea							Count for pricing only. Not an engineered bolt layout.
Fasteners	Angled joist connector at the curved header	each	16	ea							Product not chosen.
Fasteners	Stringer connector	each	10	ea							Product not chosen.
Fasteners	Structural screws, PT compatible	box covering the count	100	ea							Two at each joist bearing.
Fasteners	Deck screws, PT compatible	box covering the count	798	ea							Two at each board crossing.

Still to confirm

- Stock lengths at Winchester may replace the lengths listed.
- Veranda HDDR2022005, SKU 1001900458, is a Home Depot number, not a confirmed BMR item.
- The lower-deck walking surface is 12 in. Cut the posts on site. Beam, joist, and decking dress out at 17.5 in.
- Helical pier shaft, helix, length, torque, and bracket are not chosen. There is no concrete.
- Connector brand, bolt diameter, and gate hinges are not chosen.
- Do not read a blank price as zero.