Linda Bushel pool deck — material take-off

Preliminary Construction and Supplier Pricing Basis - Subject to Permit Review and Field Verification

Date: 2026-10-01

This take-off matches the preliminary drawing in this package.

Fifteen helical piers, sixteen joist lines, and ten stair stringers.

This sheet is quantities only. It is not a price.

Waste is the leftover on the stated stock. No extra percentage is added.

Leftover pieces are not deducted from the purchase count.

Layout sizes

Left and right are from the pool centre, standing at the stairs and looking at the pool. Out is from the pool centre toward the stairs. These sizes have not been measured on site.

Item	Value	Where it comes from
Pool	21 ft diameter	About 21 ft. Check on site.
Front edge	15'-6" out	Pool radius plus 5 ft clear
Side edges	9'-0" left and right	18 ft width
Where the sides meet the pool	5'-4 7/8" out	18 ft width meeting the pool wall
Upper deck area	116.801 sq ft	18 ft rectangle 181.650 minus the pool bite 64.849
Open pool edge	21.624 ft	Along the pool between the two sides
Main beam	13'-0" out, 6'-0" left to 6'-0" right	12 ft beam, centred
Wing end piers	9 ft left and 9 ft right, 8 ft 6 in out	Ends of the two wing beams
Header pieces	8 × 2.695 ft	Outside the pool. Joints sit 1.04 in off the wall.
Stair run	3'-8"	Four treads at 11 in. The upper deck is the top landing.
Lower deck	19'-2" to 22'-2" out	After the stair. 3 ft deep.

Lower-deck height

Intended finished walking surface 12 in. Dressed stack 1.00 + 7.25 + 9.25 = 17.50 in. Difference 5.50 in. Cut the posts on site before construction. Order the lower posts uncut.

Upper joist cut list

Stock is 2×8 × 12 ft. A pair is accepted only when both cuts plus a 1/8 in kerf fit on the stick.

Stick	Cuts (ft)	Offcut (ft)
J1	10.092	1.908
J2	10.092	1.908
J3	9.572	2.428
J4	9.572	2.428
J5	7.985	4.015
J6	7.985	4.015
J7	6.883 + 5.021	0.096
J8	6.883 + 5.021	0.096
J9	6.094 + 5.192	0.714
J10	6.094 + 5.192	0.714
J11	5.543 + 5.543	0.914

Sixteen joists. Net lineal 112.766 ft. Purchased 11 × 12 ft = 132 ft.

Joist positions from the centre, standing at the stairs and looking at the pool, with the length to the pool wall:

From centre	Length
9'-0" left	10.092 ft
8'-8" left	9.572 ft
7'-4" left	7.985 ft
6'-0" left	6.883 ft
4'-8" left	6.094 ft
3'-4" left	5.543 ft
2'-0" left	5.192 ft
0'-8" left	5.021 ft
0'-8" right	5.021 ft
2'-0" right	5.192 ft
3'-4" right	5.543 ft
4'-8" right	6.094 ft
6'-0" right	6.883 ft
7'-4" right	7.985 ft
8'-8" right	9.572 ft
9'-0" right	10.092 ft

Other 2×8 × 12 ft sticks

Use	Sticks	Allocation
Segmented header	2	4 segments of 2.695 ft on each stick
Front and main-beam blocking	3	22 pieces at 14.5 in, plus two 2.5 in closers
Wing blocking	1	4 blocks along the wings
Lower-deck joists	3	Nine 3 ft joists, three per stick after kerf
Total 2×8 × 12 ft with the upper joists	20	Offcuts not reused

5/4 × 6 cut list

Upper full-width boards: 11 pieces at 18 ft, each cut from a 20 ft board. Offcut 2 ft each. One of those boards is ripped to 5.0 in width.

Lengths beside the pool, bought once for each side, measured at the wide edge of the row:

- Row 1: 9.000 ft each side
- Row 2: 5.932 ft each side
- Row 3: 4.709 ft each side
- Row 4: 3.805 ft each side
- Row 5: 3.072 ft each side
- Row 6: 2.452 ft each side
- Row 7: 1.916 ft each side
- Row 8: 1.445 ft each side
- Row 9: 1.028 ft each side
- Row 10: 0.657 ft each side
- Row 11: 0.326 ft each side

Corner remainder below the last row: 0.60 in. No extra board.

Stock length	Cuts placed on that stick (ft)	Offcut (ft)
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	10.000	0.000
10 ft	9.000 + 0.657 + 0.326	0.017
10 ft	9.000 + 0.657 + 0.326	0.017
8 ft	5.932 + 1.916	0.153
8 ft	5.932 + 1.916	0.153
8 ft	4.709 + 3.072	0.218
8 ft	4.709 + 3.072	0.218
8 ft	3.805 + 3.805	0.389
8 ft	2.452 + 2.452 + 1.445 + 1.445	0.206
8 ft	1.028 + 1.028	5.944

Separate from that pack: 11 pieces of 5/4×6 × 20 ft for the full-width upper rows.

Guard runs

Run	Length (ft)	Treatment	Kits
Upper left side	10.092	straight run	2
Upper right side	10.092	straight run	2
Upper front left of stair	4.000	straight run	1
Upper front right of stair	4.000	straight run	1
Lower left side	3.000	straight run	1
Lower right side	3.000	straight run	1
Lower front left of gate	3.250	straight run	1
Lower front right of gate	3.250	straight run	1
Stair left	4.845	follows the stair	custom, not a 6 ft kit
Stair right	4.845	follows the stair	custom, not a 6 ft kit

Fasteners

Item	Count	Basis
Helical piers	15	One at each drawn location. Not a sonotube.
Helical-pier brackets	15	One per pier unless the pier includes the bracket
Post-to-beam connectors	15	One per post
Header connectors	16	One per upper joist

Item	Count	Basis
Stringer connectors	10	One per stringer
Beam stitch bolts	76	Two rows at 16 in on centre between posts. Count for pricing only. Diameter not chosen.
Nuts / washers	76 / 152	For those bolts
Structural screws	100	Two at each joist bearing on a beam or wing
Deck screws	798	Two per board crossing. Upper full-width 352, curve sides 160, lower deck 126, treads 160

Blocking for the guard posts, the hinge count, the bolt diameter, and the connector brand are not counted. They stay open on the request to Darcy.

Helical piers

15 helical piers, one at each drawn location. No sonotubes and no concrete. Shaft, helix, length, torque, and capacity are not chosen and are not certified.

Category waste

Category	What the waste is
Helical piers	No waste percent. Shaft, helix, and length are not specified.
Posts and brackets	A paired upper stick has about 31 in left after two 32.5 in cuts. The ninth post uses one stick. Do not cut the posts in advance.
Beams	Front offcut none on a 6 ft + 6 ft cut. Wing offcut about 1.18 ft × 2. Main and lower offcut none.
Joists, header, blocking	Upper joist stock 132 ft against net 112.766 ft. Header, blocking, and lower offcuts are on the cut list below. Offcuts are not reused to reduce the purchase.
Stringers	About 35 in left on each 8 ft piece after a 3 in end-cut allowance. Plumb-cut drawing is not included.
Decking and treads	2 ft off each 20 ft upper board, plus leftover on the shorter pieces.
Skirting	Seven 12 in cuts per stick with 1/8 in kerf leaves about 11 in. Five sticks.
Rails and guard posts	Each straight run starts a new kit. A short run leaves the rest of the 6 ft kit unused. Posts are not cut in advance. The length below the deck is not known.
Gate	None calculated.
Fasteners	No extra percent.