Linda Bushel — Pool Deck Estimate

Date: 2026-10-27

Prepared for: Linda Bushel, 12 D'Arcy's Way, Kemptville, ON K0G 1J0

Prepared by: Brayman Construction Inc., 411 St. John Street, Merrickville, ON K0G 1N0

Project

A new freestanding deck beside your above-ground pool: an upper deck at the pool, a full-width stair, and a small lower deck with a gate. Supply and installation.

Scope of work

Foundation

• Galvanized steel helical piles with adjustable steel brackets, installed by a specialist foundation contractor. No concrete footings.

• Engineer's report and compliance letter for the piles, if the town asks for it with the permit.

Structure

• Pressure-treated structural framing: built-up 2×10 beams, 2×8 joists, 6×6 posts and 2×12 stair stringers.

• Galvanized structural connectors, hangers, bolts and structural screws.

• The upper deck edge follows the curve of the pool. The deck stands on its own and is not attached to the pool.

Decking and finish

• Trex Select composite decking in Island Mist on the upper deck, the lower deck and the stair treads.

• Trex Island Mist fascia on the exposed edges, with colour-matched screws.

• Trex deck fasteners.

Upper deck, stairs and lower deck

• Upper deck about 18 ft wide, with about 5 ft of clear deck at the centre of the pool.

• 10 ft wide stairs from the upper deck down to the lower deck.

• Lower deck 10 ft wide by 3 ft deep.

Railing and gate

• Vista 42 in aluminium railing, textured black, standard pickets: upper deck sides and front, both sides of the stairs, and the lower deck.

• Matching Vista gate, 42 in high and 48 in wide, centred on the lower deck.

Installation

• Complete installation by Brayman Construction, and clean-up of construction debris.

Price

Estimate subtotal	$30,620.68
HST 13%	$3,980.69
TOTAL ESTIMATE	**$34,601.37**

Assumptions

• Pool about 21 ft in diameter and about 50 in high; all sizes are checked on site before materials are ordered.

• Access to the back yard for the pile machine (about 46 in wide; a gate or fence panel may need to be removed and replaced).

• Underground services are located before the piles go in; private buried lines (pool, power, irrigation) are pointed out by the owner.

• Normal soil. If the piles must go deeper than planned, extensions are extra and agreed with you first.
• Installation outside freezing winter conditions.
• Island Mist colour and the layout shown on our plan, confirmed with you before ordering.

Not included

• Town building-permit fee (Brayman can apply for the permit; the town's fee is billed at cost).
• Changes to the pool, its equipment or its fence, other than reinstalling a removed panel.
• A guard along the open pool edge, skirting under either deck, electrical work, lighting, landscaping or grading.
• Removal of an existing deck or structure.

Validity

Material and foundation prices come from our suppliers' current quotations and are held for a short time. This estimate is valid for 7 days. A signed agreement and deposit confirm the order.