Linda Bushel — cost sheet for Ben

Date: 2026-10-01

FOR BEN ONLY

Not a customer document. Not sent. No dollar on this sheet is a supplier price. A blank is not zero.

Quantities match the 1 Oct 2026 drawing: 15 helical piers, 16 joist lines, 10 stringers, a 5.00 in working throat, and a 12 in lower-deck walking surface. No sonotubes and no concrete.

No labour hours, equipment list, or Darcy price is on file. None was invented.

Material

Item	Quantity	Material cost
Helical pier	15	Price required
Helical-pier bracket, unless included	15	Price required
PT 6×6 × 8 ft	11	Price required
Post-to-beam connector	15	Price required
PT 2×10 × 10 ft	4	Price required
PT 2×10 × 12 ft	7	Price required
PT 2×8 × 12 ft	20	Price required
PT 2×12 × 8 ft stringer stock	10	Price required
PT 5/4×6 × 20 ft	11	Price required
PT 5/4×6 × 10 ft	17	Price required
PT 5/4×6 × 8 ft	7	Price required
PT 1×6 × 8 ft skirt	5	Price required
Veranda 37 in × 6 ft, matching the named look	10 straight kits	Price required
Custom stair guards	2	Price required
PT 4×4 × 8 ft guard posts	14	Price required
Gate, 42 in clear	1	Price required
Gate hinges and latch	Latch 1. Hinge count not stated	Price required
Stitch bolts / nuts / washers	76 / 76 / 152	Price required
Header connectors	16	Price required
Stringer connectors	10	Price required
Structural screws	100	Price required
Deck screws	798	Price required

Material total: not calculated.

The Veranda Home Depot number is not a confirmed BMR item. Bolt diameter, post bracket, and connector brand are not chosen.

Labour

Price required. No labour hours are on file for this deck. No dollar rate was applied.

Equipment

Price required. No equipment list or rate is on file.

Other direct cost

Price required. Permit fees, disposal, and delivery are not priced. Delivery address on the request is 12 D'Arcy's Way, Kemptville, ON K0G 1J0.

Allowances

The 76 stitch bolts are a count for pricing, not an engineered bolt layout. They are not priced.

No percentage waste was added. Waste is the unused length on the cut lists. Leftover pieces were not deducted from the purchase count. There is no concrete. Helical pier length is not chosen.

Direct cost

Not calculated. Material, labour, equipment, other direct cost, and allowances are not all priced.

Selling price and margin

Not calculated. This sheet does not carry a customer price or a margin. The selling price stays unissued until Darcy's quotation is in.