Linda Bushel — Internal Cost for Ben

Date: 2026-10-27

INTERNAL — NOT FOR CUSTOMER

12 D'Arcy's Way, Kemptville, ON K0G 1J0. Pool deck: upper deck, stairs and lower deck on helical piles.

All amounts are before HST. HST is shown only for cash flow: it is outside direct cost and gross margin (Brayman pricing policy). A blank is not zero. Nothing on this sheet was estimated without a written source.

Sources: BMR estimate 237147/1 (26 Oct, expires **28 Oct**), Vista quote 87915-165209 (26 Oct, MSRP), Pro Post estimate OT-2236 (6 Oct, valid 15 days — **lapsed 21 Oct**). Line-by-line comparison with issue J1: takeoff/2026-10-27-supplier-quote-reconciliation.md. The 1 Oct J1 cost sheet stays as it was.

A. BMR Winchester — materials

Group	Amount
Framing lumber (joists, header, beams, lower joists, stringers, posts, blocking)	$1,361.71
Structural hardware (post ties, hangers, stringer hangers, 3/8 in bolts, nuts, washers, structural screws)	$389.35
Trex Select Island Mist deck boards (upper, lower, stair treads)	$4,827.20
Trex Island Mist fascia (5 × 1×8 × 12 ft under Stairs, 5 × 1×12 × 12 ft under Other)	$1,666.80
Trex fasteners and fascia screw kit	$431.03
BMR quoted materials	**$8,676.09**
HST (cash flow only)	$1,127.89

Confirm with Darcy before ordering (the estimate says the customer verifies quantities):

- Stringers: 4 × 2×12 × 10 ft gives 4 stringers; J1 has 10.
- Upper joist stock: cut to J1's lengths, the quoted sticks give at most 14 of the 16 joists (J1 needs 7 × 12 ft; 4 are quoted).
- Header: 3 × 2×8 × 8 ft gives 6 of the 8 header pieces.
- Posts: 7 sticks quoted. By J1's cutting rules, 15 posts need 11 sticks and an 11-pile layout needs 8 (see the foundation decision).
- Hangers: 14 skewed hangers printed "2×6" for 16 2×8 joists; 11 extra 2×8 hangers with no stated use.
- Fascia: what the 1×8 (stairs) and 1×12 (other) pieces are for. J1 had 44.184 ft of rim fascia and no riser boards.
- Nuts and washers: 75 / 150 against 100 bolts.
- Lower-deck skirt, 5 × PT 1×6 × 8 ft: not on the estimate.

B. Vista railing (through BMR)

Item	Amount
Vista quotation, total **MSRP**	$3,851.49
Relationship to BMR	**Additional.** BMR's priced lines add to $8,676.09 on their own; the Vista package is "See separate quote" with no amount.
Brayman's payable price	**Not established.** MSRP is a list price, not Brayman's cost.
Used on this sheet	**$3,851.49 (MSRP) as Brayman's cost** until Darcy gives the price BMR will invoice. A lower BMR price only increases Brayman's margin; Linda's price is unaffected.

CONFIRM WITH DARCY — Vista payable cost / relationship to BMR estimate. Also confirm: gate hinges and latch included, post-base fasteners, delivery.

Vista 42 in aluminium replaces J1's 37 in Veranda kits, the 14 PT 4×4 guard posts and the custom stair guards. Its gate is 48 in. Each post needs solid blocking under the base plate (not counted).

C. Pro Post Foundations — helical piles

Item	Qty	Amount
Helical pile 2-3/8 in × 8 in blade × 7 ft, flat bracket included	10 × $295	$2,950.00
Helical pile 2-3/8 in × 10 in blade × 7 ft, flat bracket included	1 × $315	$315.00
Travel fee	1	$85.00
Piles and travel (11 piles)		$3,350.00
Engineer report and compliance letter — conditional on the town; **included in the cost used**	1	$400.00
Foundation cost used		**$3,750.00**
HST (cash flow only)		$487.50
Deposit to book (50% of $4,237.50)		$2,118.75

Not included, if needed: pile extensions $240 each, U-brackets $35 each, excavation $105/h, welder $145/h, winter installation $95/h, waiting or unmarked piles $95/h, revisions to the engineer report $100.

FOUNDATION QUANTITY CONFIRMATION REQUIRED — J1 = 15; Pro Post engineered quotation = 11. Pro Post's 11 piles sit on the same deck outline but a different beam layout. Choose: adopt the 11 piles and re-draw the framing to Pro Post's beam lines, or keep 15 and get a revised Pro Post price. This sheet uses the written 11-pile price ($3,750 including the engineer report).

OT-2236 was valid to 21 Oct. Reconfirm the price with Pro Post before the deposit.

The earlier working figure of $350 per pier is superseded by OT-2236 and is not used.

D. Labour

Searched 27 Oct 2026 for anything that can calculate Linda's labour:

Source	What it has for this deck
This case (P1, CT, J1, 6 Oct cost request)	Quantities only. No hours.
app/services/deck_framing_quantity.py and the deck take-off engine	Member counts only; by design "does not invent a labour production rate".
Production labour tasks and production-rate standards (27 Oct copy of the Production database)	7 tasks, all UAT or concrete; 1 production rate, synthetic and withdrawn. No deck, framing, decking or railing rate.
Production historical estimates (24) and their labour lines (120)	Slabs, ICF, a garage, a renovation, a concrete gate. No deck, stair or railing labour.
Direct labour cost rate	Platform policy and the Production rate standard: $65.00 per man-hour (29 Aug 2026).

Rate used: $75.00 per hour — Ben's labour rate, set by Joel on 27 Oct 2026. The platform pricing policy (docs/pricing-policy.md) and the Production rate standard still say $65 and are updated separately; this case does not change them.

Hours: no governed method exists, so the hours are built up task by task from the take-off below and proposed for Joel's approval. Change any line and the price follows.

E. Delivery and carrying

BMR: "Delivery extra. Carrying extra." No amount on any document. Treated as $0.00 (absorbed) unless Joel gives an amount.

F. Equipment

$0.00. Pro Post brings its own installation machine; Brayman's work needs hand and power tools only.

G. Permit and engineering

Item	Treatment
Pro Post engineer report and compliance letter	$400.00, **included** in the $3,750 foundation cost (the conservative case).
Town building-permit fee	Excluded from Linda's price, as in J1; billed at cost if Brayman applies.

<!-- PRICE:BEGIN -->

Labour build-up (proposed for Joel's approval)

Built from the J1 take-off and the supplier quantities. No governed deck production rate exists, so each line is a proposed allowance for a two-person crew: approve it or change any line.

Task	Quantity basis	Man-hours
Layout, mark the pile locations, meet Pro Post on site	11 pile locations; deck and stair lines	8
Posts and beams	11 posts cut on brackets; built-up 2×10 beams (7 × 12 ft + 4 × 10 ft), 3/8 in carriage bolts	16
Upper-deck framing	16 joists cut to the pool curve, 8-piece curved header with 14 skewed hangers, blocking	24
Lower-deck framing	9 joists 3 ft, lower beam, blocking, lower posts cut on site	8
Stairs	10 ft wide, 4 treads, 5 risers; stringers cut and hung	16
Trex decking	about 147 sq ft (upper 116.8 + lower 30), every board scribed to the pool curve on the upper deck	16
Stair treads and risers (Trex)	8 tread boards, 5 riser boards 10 ft	8
Trex fascia	about 44 ft of exposed rim, colour-matched screws	6
Railing blocking	solid blocking under each Vista post base	4
Vista railing and gate	11 sections, 14 posts on base plates, pickets, 48 in gate	16
Unload and carry materials	BMR delivery to the back yard (carrying is extra from BMR)	4
Clean-up and final walk-through	debris, offcuts, punch list	4
Total	Two-person crew, about 8.1 working days	**130**

Direct cost and selling price

Cost component	Cost (pre-HST)	Evidence / status
BMR materials	$8,676.09	Written: estimate 237147/1, 26 Oct 2026
Vista railing and gate	$3,851.49	Written: quote 87915-165209 at **MSRP**; additional to BMR. Used as Brayman's cost until Darcy gives BMR's price. Any discount lowers cost and raises margin; the price to Linda does not change.
Pro Post helical foundation (11 piles, travel, engineer report)	$3,750.00	Written: OT-2236. Includes the $400 report in full (conditional on the town). Pile count to confirm; reconfirm the lapsed quote.
Brayman labour	$9,750.00	130 man-hours × $75 (Ben's rate). Build-up below; Joel approves or changes it.
Delivery / carrying	$0.00	BMR: delivery and carrying extra; no amount on any document. $0 (absorbed) until Darcy gives one
Equipment	$0.00	None: Pro Post brings its own machine; hand tools only
Permit fee	$0.00	Excluded from Linda's price (as in J1); billed at cost if Brayman pulls the permit
TOTAL DIRECT COST	**$26,027.58**	

Governed pricing: ORG-001-TRUE-GM-15, **true gross margin 15%** (not markup). Selling price = direct cost ÷ 0.85.

	Amount
Total direct cost	$26,027.58
Gross profit	$4,593.10

	Amount
Selling price before HST	**$30,620.68**
HST 13%	$3,980.69
Linda estimate total	**$34,601.37**
Resulting true gross margin	15.00%

Every 10 man-hours more or less changes the price before HST by $882.35.

<!-- PRICE:END -->

Dates

• **28 Oct 2026** — BMR prices held only if the award is confirmed by then.

• OT-2236 lapsed 21 Oct — reconfirm with Pro Post.