Linda Bushel — Internal Cost for Ben

Date: 2026-10-27

INTERNAL — NOT FOR CUSTOMER

12 D'Arcy's Way, Kemptville, ON K0G 1J0. Pool deck: upper deck, stairs and lower deck on helical piles.

All amounts are before HST. HST is shown only for cash flow: it is outside direct cost and gross margin (Brayman pricing policy). A blank is not zero. Nothing on this sheet was estimated without a written source.

Sources: BMR estimate 237147/1 (26 Oct, expires **28 Oct**), Vista quote 87915-165209 (26 Oct, MSRP), Pro Post estimate OT-2236 (6 Oct, valid 15 days — **lapsed 21 Oct**). Line-by-line comparison with issue J1: takeoff/2026-10-27-supplier-quote-reconciliation.md. The 1 Oct J1 cost sheet stays as it was.

A. BMR Winchester — materials

Group	Amount
Framing lumber (joists, header, beams, lower joists, stringers, posts, blocking)	$1,361.71
Structural hardware (post ties, hangers, stringer hangers, 3/8 in bolts, nuts, washers, structural screws)	$389.35
Trex Select Island Mist deck boards (upper, lower, stair treads)	$4,827.20
Trex Island Mist fascia (5 × 1×8 × 12 ft under Stairs, 5 × 1×12 × 12 ft under Other)	$1,666.80
Trex fasteners and fascia screw kit	$431.03
BMR quoted materials	**$8,676.09**
HST (cash flow only)	$1,127.89

Confirm with Darcy before ordering (the estimate says the customer verifies quantities):

- Stringers: 4 × 2×12 × 10 ft gives 4 stringers; J1 has 10.
- Upper joist stock: cut to J1's lengths, the quoted sticks give at most 14 of the 16 joists (J1 needs 7 × 12 ft; 4 are quoted).
- Header: 3 × 2×8 × 8 ft gives 6 of the 8 header pieces.
- Posts: 7 sticks quoted. By J1's cutting rules, 15 posts need 11 sticks and an 11-pile layout needs 8 (see the foundation decision).
- Hangers: 14 skewed hangers printed "2×6" for 16 2×8 joists; 11 extra 2×8 hangers with no stated use.
- Fascia: what the 1×8 (stairs) and 1×12 (other) pieces are for. J1 had 44.184 ft of rim fascia and no riser boards.
- Nuts and washers: 75 / 150 against 100 bolts.
- Lower-deck skirt, 5 × PT 1×6 × 8 ft: not on the estimate.

B. Vista railing (through BMR)

Item	Amount
Vista quotation, total **MSRP**	$3,851.49
Relationship to BMR	**Additional.** BMR's priced lines add to $8,676.09 on their own; the Vista package is "See separate quote" with no amount.
Brayman's payable price	**Not established.** MSRP is a list price, not Brayman's cost.
Used on this sheet	**$3,851.49 (MSRP) as Brayman's cost** until Darcy gives the price BMR will invoice. A lower BMR price only increases Brayman's margin; Linda's price is unaffected.

CONFIRM WITH DARCY — Vista payable cost / relationship to BMR estimate. Also confirm: gate hinges and latch included, post-base fasteners, delivery.

Vista 42 in aluminium replaces J1's 37 in Veranda kits, the 14 PT 4×4 guard posts and the custom stair guards. Its gate is 48 in. Each post needs solid blocking under the base plate (not counted).

C. Pro Post Foundations — helical piles

Item	Qty	Amount
Helical pile 2-3/8 in × 8 in blade × 7 ft, flat bracket included	10 × $295	$2,950.00
Helical pile 2-3/8 in × 10 in blade × 7 ft, flat bracket included	1 × $315	$315.00
Travel fee	1	$85.00
Piles and travel (11 piles)		$3,350.00
Engineer report and compliance letter — conditional on the town; **included in the cost used**	1	$400.00
Foundation cost used		**$3,750.00**
HST (cash flow only)		$487.50
Deposit to book (50% of $4,237.50)		$2,118.75

Not included, if needed: pile extensions $240 each, U-brackets $35 each, excavation $105/h, welder $145/h, winter installation $95/h, waiting or unmarked piles $95/h, revisions to the engineer report $100.

FOUNDATION QUANTITY CONFIRMATION REQUIRED — J1 = 15; Pro Post engineered quotation = 11. Pro Post's 11 piles sit on the same deck outline but a different beam layout. Choose: adopt the 11 piles and re-draw the framing to Pro Post's beam lines, or keep 15 and get a revised Pro Post price. This sheet uses the written 11-pile price ($3,750 including the engineer report).

OT-2236 was valid to 21 Oct. Reconfirm the price with Pro Post before the deposit.

The earlier working figure of $350 per pier is superseded by OT-2236 and is not used.

D. Labour

Searched 27 Oct 2026 for anything that can calculate Linda's labour:

Source	What it has for this deck
This case (P1, CT, J1, 6 Oct cost request)	Quantities only. No hours.
app/services/deck_framing_quantity.py and the deck take-off engine	Member counts only; by design "does not invent a labour production rate".
Production labour tasks and production-rate standards (27 Oct copy of the Production database)	7 tasks, all UAT or concrete; 1 production rate, synthetic and withdrawn. No deck, framing, decking or railing rate.
Production historical estimates (24) and their labour lines (120)	Slabs, ICF, a garage, a renovation, a concrete gate. No deck, stair or railing labour.
Direct labour cost rate	**$65.00 per man-hour**, APPROVED (ORG-001, 29 Aug 2026; docs/pricing-policy.md).

Result: no governed method gives Linda's labour hours. The rate is governed; the hours are a decision for Joel. The table below prices the job at 80, 100, 120 and 140 man-hours so that one number finishes it.

E. Delivery and carrying

BMR: "Delivery extra. Carrying extra." No amount on any document. Treated as $0.00 (absorbed) unless Joel gives an amount.

F. Equipment

$0.00. Pro Post brings its own installation machine; Brayman's work needs hand and power tools only.

G. Permit and engineering

Item	Treatment
Pro Post engineer report and compliance letter	$400.00, **included** in the $3,750 foundation cost (the conservative case).
Town building-permit fee	Excluded from Linda's price, as in J1; billed at cost if Brayman applies.

<!-- PRICE:BEGIN -->

Direct cost and selling price

Cost component	Cost (pre-HST)	Evidence / status
BMR materials	$8,676.09	Written: estimate 237147/1, 26 Oct 2026
Vista railing and gate	$3,851.49	Written: quote 87915-165209 at **MSRP**; additional to BMR. Used as Brayman's cost until Darcy gives BMR's price. Any discount lowers cost and raises margin; the price to Linda does not change.
Pro Post helical foundation (11 piles, travel, engineer report)	$3,750.00	Written: OT-2236. Includes the $400 report in full (conditional on the town). Pile count to confirm; reconfirm the lapsed quote.
Brayman labour	**NOT SET**	**Need Joel to approve the total man-hours** (rate $65, governed). No governed deck production rate, Linda labour estimate or Brayman deck history exists.
Delivery / carrying	$0.00 unless Joel gives an amount	BMR: "delivery extra, carrying extra"; no amount on any document
Equipment	$0.00	None: Pro Post brings its own machine
Permit fee	$0.00	Excluded from Linda's price (as in J1)
Total direct cost before labour	**$16,277.58**	All three written supplier amounts

Governed pricing: ORG-001-TRUE-GM-15, **true gross margin 15%** (not markup). Selling price = direct cost ÷ 0.85.

Choose the man-hours (2-person crew; 8 h days: 80 h = 5 days, 100 h = 6¼ days, 120 h = 7½ days, 140 h = 8¾ days):

Man-hours	Labour	Total direct cost	Gross profit	Selling price before HST	HST 13%	Linda total
80	$5,200.00	$21,477.58	$3,790.16	$25,267.74	$3,284.81	$28,552.55
100	$6,500.00	$22,777.58	$4,019.57	$26,797.15	$3,483.63	$30,280.78
120	$7,800.00	$24,077.58	$4,248.98	$28,326.56	$3,682.45	$32,009.01
140	$9,100.00	$25,377.58	$4,478.40	$29,855.98	$3,881.28	$33,737.26

Each man-hour adds $65.00 of cost and $76.47 to the price before HST ($86.41 with HST).

<!-- PRICE:END -->

Dates

- **28 Oct 2026** — BMR prices held only if the award is confirmed by then.
- OT-2236 lapsed 21 Oct — reconfirm with Pro Post.