BRAYMAN CONSTRUCTION INC.
411 St. John Street, Merrickville, ON K0G 1N0

CUSTOMER DETAILED COST ESTIMATE

DETAILED ESTIMATE

Client	Linda Bushel	**Project**	Bushel Rear Deck (pool deck)
Site	12 D'Arcy's Way, Kemptville, ON K0G 1J0	**Date**	2026-10-27

Material / Package	Description	Price
Pressure-treated structural framing	Built-up 2×10 beams, 2×8 joists, 6×6 posts, curved header, blocking and 2×12 stair stringers	$1,556.24
Structural hardware and connectors	Galvanized joist and skewed hangers, post bases, carriage bolts and structural screws	$444.97
Trex Select decking, Island Mist	Composite decking for the upper deck, the lower deck and the stair treads and risers	$5,516.80
Trex fascia, Island Mist	Fascia on the exposed deck and stair edges	$1,904.91
Trex fasteners and fascia screws	Hidden deck fasteners and colour-matched fascia screws	$492.61
Vista 42 in aluminium railing and gate	Textured black, standard pickets: upper deck sides and front, both sides of the stairs, lower deck; 42 in high, 48 in wide gate	$4,401.70
Helical pile foundation — 11 piles, supply and installation	Galvanized steel helical piles with brackets installed by a specialist foundation contractor, including mobilization and the engineer's report and compliance letter if the town requires it	$4,285.71
Total materials and foundation		$18,602.94

Labour by Task

Labour Task	Hours	Price
Layout and mark the pile locations	4	$342.86
Posts and beams	16	$1,371.43
Upper-deck framing	24	$2,057.14
Lower-deck framing	8	$685.71
Stairs	16	$1,371.43
Trex decking	16	$1,371.43
Stair treads and risers (Trex)	8	$685.71
Trex fascia	5	$428.57
Railing blocking	4	$342.86
Vista railing and gate	16	$1,371.43

BRAYMAN CONSTRUCTION INC.
411 St. John Street, Merrickville, ON K0G 1N0

Labour Task	Hours	Price
Unload and carry materials	4	$342.86
Clean-up and final walk-through	4	$342.86
Total labour	125	$10,714.29

Price Summary

Price Component	Amount
Materials and foundation	$18,602.94
Labour (125 hours, two-person crew)	$10,714.29
Estimate subtotal	$29,317.23
HST 13%	$3,811.24
Total including HST	$33,128.47
Pricing	Material and foundation prices are confirmed with our suppliers when the work is ordered. This estimate is valid for 7 days.
Not included	Town permit fee (billed at cost), electrical, plumbing, painting, grading and landscaping, a guard along the open pool edge, skirting, and pile extensions if deeper piles are needed (agreed with you first)

Prices include the materials, equipment, labour, supervision and overhead for the scope described. HST is shown separately.