Linda Bushel — Pool Deck Estimate

Date: 2026-10-27

Prepared for: Linda Bushel, 12 D'Arcy's Way, Kemptville, ON K0G 1J0

Prepared by: Brayman Construction Inc., 411 St. John Street, Merrickville, ON K0G 1N0

Price: to be confirmed. Our suppliers have quoted the main materials and the foundation. Our final price follows once the last supplier prices, the foundation layout and the installation date are confirmed.

Project

A new freestanding deck beside your above-ground pool: an upper deck at the pool, a full-width stair, and a small lower deck with a gate.

Scope of work

Foundation

• Galvanized steel helical piles, screwed into the ground by a specialist foundation contractor, with adjustable steel brackets. No concrete footings.

• Pile size, number and locations to be confirmed with the foundation contractor before installation.

Structure

• Pressure-treated structural framing: built-up 2×10 beams, 2×8 joists, 6×6 posts and 2×12 stair stringers.

• Galvanized structural connectors, hangers, bolts and structural screws.

• The upper deck edge follows the curve of the pool. The deck stands on its own and is not attached to the pool.

Decking and finish

• Trex Select composite decking in **Island Mist** on the upper deck, the lower deck and the stair treads.

• Trex Island Mist fascia on the exposed edges, fastened with colour-matched screws.

• Trex deck fasteners.

Upper deck, stairs and lower deck

• Upper deck about 18 ft wide, with about 5 ft of clear deck at the centre of the pool.

• 10 ft wide stairs from the upper deck down to the lower deck.

• Lower deck 10 ft wide by 3 ft deep, with a pressure-treated 1×6 skirt around it.

Railing and gate

• Vista 42 in aluminium railing, textured black, standard pickets, on the upper deck sides and front, both sides of the stairs, and the lower deck.

• Matching 42 in high Vista gate, 48 in wide, centred on the lower deck.

Labour

• Supply and installation of everything listed above, by Brayman Construction.

• Site clean-up of construction debris on completion.

Assumptions

• Pool about 21 ft in diameter and about 50 in high. All sizes are checked on site before materials are ordered.

• Clear access to the back yard for the pile-installation machine (about 46 in wide; a gate or fence panel may need to be removed and replaced).

• Underground services are located before the piles are installed. Any private buried lines (for example pool, power or irrigation) are pointed out by the owner.

• Normal soil conditions. If the foundation contractor finds the piles must go deeper to reach the required resistance, pile extensions are an additional cost, agreed with you first.

• Installation outside of freezing winter conditions, unless agreed otherwise.

Not included

• Town building-permit fees, and an engineer's report or compliance letter if the town asks for one. Brayman can arrange both; their cost is confirmed before work starts.

• Changes to the pool, its equipment or its fence, other than reinstalling a removed panel.

• A guard along the open pool edge of the deck.

• Electrical work, lighting, landscaping, sod or grading.

• Removal of an existing deck or structure.

• Skirting under the upper deck.

Permits and pool safety

The work follows the requirements of the town's building permit. Pool-enclosure rules (including fence and gate height and self-closing, self-latching gates) are confirmed with the town during the permit review. Any change the town requires is discussed with you before it is made.

Next steps

1. Confirm the design and the Island Mist colour.
2. We confirm the final supplier prices and the installation date, and send you the final price.
3. On your approval, we book the foundation contractor and order the materials.

This is an estimate, not a contract. Prices from our suppliers are time-limited; the final price is confirmed in writing before any work begins.