Linda Bushel — Internal Cost for Ben

Date: 2026-10-27

INTERNAL — NOT FOR CUSTOMER

12 D'Arcy's Way, Kemptville, ON K0G 1J0. Pool deck: upper deck, stairs and lower deck on helical piles.

All amounts are before HST. HST is shown only for cash flow: it is outside direct cost and gross margin (Brayman pricing policy). A blank is not zero. Nothing on this sheet was estimated without a written source.

Sources: BMR estimate 237147/1 (26 Oct, expires **28 Oct**), Vista quote 87915-165209 (26 Oct, MSRP), Pro Post estimate OT-2236 (6 Oct, valid 15 days — **lapsed 21 Oct**). Line-by-line comparison with issue J1: takeoff/2026-10-27-supplier-quote-reconciliation.md. The 1 Oct J1 cost sheet stays as it was.

A. BMR Winchester — materials

Group	Amount
Framing lumber (joists, header, beams, lower joists, stringers, posts, blocking)	$1,361.71
Structural hardware (post ties, hangers, stringer hangers, 3/8 in bolts, nuts, washers, structural screws)	$389.35
Trex Select Island Mist deck boards (upper, lower, stair treads)	$4,827.20
Trex Island Mist fascia (5 × 1×8 × 12 ft under Stairs, 5 × 1×12 × 12 ft under Other)	$1,666.80
Trex fasteners and fascia screw kit	$431.03
BMR quoted materials	**$8,676.09**
HST (cash flow only)	$1,127.89

Confirm with Darcy before ordering (the estimate says the customer verifies quantities):

- Stringers: 4 × 2×12 × 10 ft gives 4 stringers; J1 has 10.
- Upper joist stock: cut to J1's lengths, the quoted sticks give at most 14 of the 16 joists (J1 needs 7 × 12 ft; 4 are quoted).
- Header: 3 × 2×8 × 8 ft gives 6 of the 8 header pieces.
- Posts: 7 sticks quoted. By J1's cutting rules, 15 posts need 11 sticks and an 11-pile layout needs 8 (see the foundation decision).
- Hangers: 14 skewed hangers printed "2×6" for 16 2×8 joists; 11 extra 2×8 hangers with no stated use.
- Fascia: what the 1×8 (stairs) and 1×12 (other) pieces are for. J1 had 44.184 ft of rim fascia and no riser boards.
- Nuts and washers: 75 / 150 against 100 bolts.
- Lower-deck skirt, 5 × PT 1×6 × 8 ft: not on the estimate.

B. Vista railing (through BMR)

Item	Amount
Vista quotation, total **MSRP**	$3,851.49
Relationship to BMR	**Additional.** BMR's priced lines add to $8,676.09 on their own; the Vista package is "See separate quote" with no amount.
Brayman's payable price	**Not established.** MSRP is a list price, not Brayman's cost.
Used on this sheet	**$3,851.49 as an ALLOWANCE**, until Darcy gives the price BMR will invoice. Not final.

CONFIRM WITH DARCY — Vista payable cost / relationship to BMR estimate. Also confirm: gate hinges and latch included, post-base fasteners, delivery.

Vista 42 in aluminium replaces J1's 37 in Veranda kits, the 14 PT 4×4 guard posts and the custom stair guards. Its gate is 48 in. Each post needs solid blocking under the base plate (not counted).

C. Pro Post Foundations — helical piles

Item	Qty	Amount
Helical pile 2-3/8 in × 8 in blade × 7 ft, flat bracket included	10 × $295	$2,950.00
Helical pile 2-3/8 in × 10 in blade × 7 ft, flat bracket included	1 × $315	$315.00
Travel fee	1	$85.00
Committed foundation cost (11 piles)		**$3,350.00**
Engineer report and compliance letter — **conditional**: required only if the town asks for it with the permit application	1	$400.00 (shown separately)
Quotation subtotal		$3,750.00
HST (cash flow only)		$487.50
Deposit to book (50% of $4,237.50)		$2,118.75

Not included, if needed: pile extensions $240 each, U-brackets $35 each, excavation $105/h, welder $145/h, winter installation $95/h, waiting or unmarked piles $95/h, revisions to the engineer report $100.

FOUNDATION QUANTITY CONFIRMATION REQUIRED — J1 = 15; Pro Post engineered quotation = 11. Pro Post's 11 piles sit on the same deck outline but a different beam layout. Choose: adopt the 11 piles and re-draw the framing to Pro Post's beam lines, or keep 15 and get a revised Pro Post price. This sheet uses the written 11-pile price.

OT-2236 was valid to 21 Oct. Reconfirm the price with Pro Post before the deposit.

The earlier working figure of $350 per pier is superseded by OT-2236 and is not used.

D. Labour

LABOUR HOURS REQUIRED. No Linda labour hours are in the case, and no approved Brayman deck assembly calculates them. None were invented.

Governed Brayman direct labour rate: **$65 per man-hour** (pricing policy, 25 Aug 2026).

Labour cost = man-hours × $65.

E. Delivery and carrying

PRICE REQUIRED. BMR: "Delivery extra. Carrying extra." Vista delivery not stated.

F. Equipment

PRICE REQUIRED (or "none"). Pro Post brings its own installation machine; it needs 46 in straight access, with a gate or fence panel removed.

G. Permit and engineering

Item	Status
Pro Post engineer report and compliance letter	$400.00, conditional on the town (section C). Not counted twice.
Town building-permit fee	**PRICE REQUIRED.** The J1 customer estimate excluded permit fees; decide whether Linda's price includes them.
Other engineering	None in the case. The J1 drawings carry no engineering seal.

Direct cost summary

Line	Amount	Status
BMR materials	$8,676.09	Written. Quantities to confirm.
Pro Post piles and travel (11 piles)	$3,350.00	Written. Pile count to confirm; validity lapsed.
Subtotal, firm written prices	**$12,026.09**	
Vista railing	$3,851.49	**ALLOWANCE** at MSRP — confirm with Darcy
Subtotal with the railing allowance	**$15,877.58**	

Line	Amount	Status
Pro Post engineer report (conditional)	$400.00	Include only if the town requires it
Labour	—	LABOUR HOURS REQUIRED × $65
Delivery and carrying	—	PRICE REQUIRED
Equipment	—	PRICE REQUIRED
Town permit fee	—	PRICE REQUIRED / decision
Lower-deck skirt, gate hardware (if not in the gate), disposal	—	PRICE REQUIRED
Direct cost	**Not complete**	

Nothing above is counted twice: Vista is outside BMR, the pile brackets are inside the pile price, and the engineer report is shown once, apart from the committed foundation cost.

Selling price (internal)

Governed method: **true gross margin, 15%** (pricing policy, 25 Aug 2026). Not a markup.

Selling price = direct cost ÷ (1 – 0.15) = direct cost ÷ 0.85

	Direct cost	Selling price	Gross profit	Gross margin
Supplier and subcontract costs only, with the railing allowance (**not a price** — labour and the other lines are missing)	$15,877.58	$18,679.51	$2,801.93	15.0%
Each man-hour of labour adds	$65.00	$76.47	$11.47	15.0%

Final selling price = ($15,877.58 + 65 × man-hours + delivery + equipment + permit + other) ÷ 0.85, with the Vista and engineer-report lines replaced by their confirmed amounts. **Not issued.**

Dates

• **28 Oct 2026** — BMR prices held only if the award is confirmed by then.

• OT-2236 lapsed 21 Oct — reconfirm with Pro Post.