Linda Bushel — supplier quotation reconciliation

Date: 2026-10-27

Compares the three written supplier documents with the 1 Oct 2026 issue J1 take-off. J1 is not changed. Prices are pre-HST.

Source	Document	Amount
BMR Winchester	Estimate 237147/1, 26 Oct 2026, expires 28 Oct 2026	$8,676.09
Vista (through BMR)	Quote 87915-165209, 26 Oct 2026, **MSRP**	$3,851.49
Pro Post Foundations	Estimate OT-2236, 6 Oct 2026, valid 15 days (lapsed 21 Oct)	$3,750.00 (incl. $400 conditional engineer report)

Status words: **priced** (written price, quantity matches J1), **variance** (written price, quantity or product differs from J1), **substitution** (a different product does the same job), **conditional**, **optional**, **not priced** (no written price), **superseded**.

Framing

Requirement	J1 qty	Supplier qty	Supplier	SKU / product	Unit	Extension	Status / explanation
Upper joists, 2×8	11 × 12 ft (132 ft; net 112.766 ft for 16 joists)	4 × 12 ft, 2 × 10 ft, 6 × 8 ft (116 ft)	BMR	0749011 / 0749002 / 0748997	23.924 / 19.911 / 15.916	231.00	**Variance — short by about 2 joists.** J1's cut plan needs 7 × 12 ft (its two 10.092 ft outer joists and its five paired sticks). Cut to J1's lengths, the quoted 4 × 12, 2 × 10 and 6 × 8 ft give at most 14 of the 16 joists (BMR also quotes 14 skewed hangers). Confirm the joist stock with Darcy against the cut list.
Curved header, 2×8	2 × 12 ft (8 pieces × 2.695 ft)	3 × 8 ft	BMR	0748997	15.916	47.75	**Variance.** An 8 ft stick gives two 2.695 ft pieces, so 3 sticks give 6 of the 8 pieces. Confirm.
Beams, 2-ply 2×10	7 × 12 ft + 4 × 10 ft	7 × 12 ft + 4 × 10 ft	BMR	0749066 / 0749057	39.576 / 32.751	408.03	**Priced.** Matches J1. Beam layout depends on the foundation decision below.
Lower-deck joists, 2×8	3 × 12 ft	3 × 12 ft	BMR	0749011	23.924	71.77	**Priced.** Matches J1.

Requirement	J1 qty	Supplier qty	Supplier	SKU / product	Unit	Extension	Status / explanation
Stair stringers, 2×12	10 × 8 ft (10 stringers)	4 × 10 ft	BMR	0749109	44.126	176.50	**Variance.** J1 leaves about 35 in on each 8 ft piece after a 3 in end-cut allowance, so a stringer takes about 61 in; one 10 ft stick gives one stringer: 4 stringers, not 10. Confirm with Darcy and Ben.
Posts, 6×6	11 × 8 ft (15 posts)	7 × 8 ft	BMR	0749190	38.338	268.37	**Variance.** By J1's rules (two upper posts per stick, each lower post a full stick, ordered uncut) J1's 15 posts need 11 sticks and Pro Post's 11 posts (7 upper, 4 lower) need 8. BMR quotes 7: short for either. See Foundation.
Blocking	4 × 2×8 × 12 ft	6 × 2×10 × 8 ft	BMR	0749048	26.381	158.29	**Substitution.** 2×10 blocking in place of 2×8. Confirm.
Post-to-beam connector	15	30 deck post ties	BMR	SDJT14-TZ	2.291	68.73	**Variance.** 30 ties (two per post would be 22 for 11 posts, 30 for 15). Confirm.
Joist-to-header connector	16	14 skewed hangers (7 L + 7 R)	BMR	SKH26L-TZ / SKH26R-TZ, printed "2×6"	6.247	87.46	**Variance.** Count 14 against 16, and the hanger is printed for 2×6 where the joists are 2×8. Confirm size and count.
Joist hangers	not in J1	11	BMR	JUS28-TZ (2×8 slant-nail)	1.187	13.06	**Variance.** Not in J1. Purpose not stated.
Stringer connectors	10	10	BMR	CSH-TZ concealed stringer hanger	2.291	22.91	**Priced.** Count matches J1's 10 stringers; see the stringer variance.
Stitch bolts / nuts / washers	76 / 76 / 152 (diameter open)	100 / 75 / 150, 3/8 in × 4 in carriage	BMR	2094562 / 2093387 / 2680633	packages	136.51	**Variance.** Diameter now 3/8 in. 75 nuts and 150 washers are one nut and two washers short of J1's 76 bolts.
Structural screws	100	100 (2 × 50)	BMR	0017968 T40 3 in	30.342 / pk	60.68	**Priced.**

Deck finish

Requirement	J1 qty	Supplier qty	Supplier	SKU / product	Unit	Extension	Status / explanation
Upper deck boards	11 × 20 ft + side pieces (part of 17 × 10 ft and 7 × 8 ft)	11 × 20 ft + 11 × 12 ft	BMR	Trex Select Island Mist 1×6	188.48 / 113.28	3,319.36	**Priced, stock re-planned.** Darcy priced Island Mist; Linda has not yet confirmed the colour.
Lower deck boards	in the 10 ft pack	4 × 20 ft	BMR	Trex Select Island Mist 1×6×20	188.48	753.92	**Priced, stock re-planned.**
Stair treads (4 treads × 2 boards × 10 ft)	in the 10 ft pack	4 × 20 ft	BMR	Trex Select Island Mist 1×6×20	188.48	753.92	**Priced.** 4 × 20 ft = 8 × 10 ft = the 8 tread boards.
All Trex boards, lineal	446 ft (11×20 + 17×10 + 7×8)	512 ft (19×20 + 11×12)				4,827.20	Supplier lineal is 66 ft more than J1.
Stair risers (by group on the estimate)	not in J1	5 × 1×8 × 12 ft fascia	BMR	Trex fascia Island Mist 1×8×12	124.379	621.90	**Variance.** Grouped under "Stairs": five pieces match the five 10 ft risers. J1 did not list riser boards. Confirm.
Rim fascia	44.184 ft, width open	5 × 1×12 × 12 ft (60 ft)	BMR	Trex fascia Island Mist 1×12×12	208.98	1,044.90	**Variance.** Grouped under "Other", no use stated. 60 ft covers the 44.184 ft rim. Confirm the use and the 12 in width.
Deck fasteners	798 (two per crossing)	6 boxes, 50 sq ft each (300 sq ft)	BMR	Trex deck fasteners 0022924	56.22	337.32	**Priced.** About 184 sq ft of walking surface (116.8 upper + 30 lower + about 37 treads).
Fascia screws and caps	not counted	1 kit	BMR	0022490	93.712	93.71	**Priced.**
Lower-deck skirt, PT 1×6 × 8 ft	5	—	—	—	—	—	**Not priced.** Not on the BMR estimate.

Railing

Requirement	J1 qty	Supplier qty	Supplier	SKU / product	Unit	Extension (MSRP)	Status / explanation
Level guard	10 Veranda 37 in × 6 ft kits	7 rails (5 × 5 ft, 2 × 7 ft), 4 end, 4 corner, 2 mid posts, 2 + 5 picket packages, 4 level brackets	Vista via BMR	PB7453/7455/5468/5469 /5470/7777/7779/7477	MSRP	2,560.72	**Substitution.** Vista 42 in aluminium replaces the 37 in Veranda kit. Runs follow the J1 layout (sections 1–2, 4–5, 7–8, 10–11; section 6 is the gate).

Requirement	J1 qty	Supplier qty	Supplier	SKU / product	Unit	Extension (MSRP)	Status / explanation
Stair guard	2 custom	1 × 8 ft stair rail (cut to two 40.91 in), 2 top + 2 bottom stair posts, 2 stair picket packages	Vista via BMR	PB5484/5733/5735/7773	MSRP	655.93	**Substitution.** Sections 3 and 9.
Gate	1, 42 in clear	1 × 42 in high, 48 in gate	Vista via BMR	PB7517XB	423.99	423.99	**Substitution.** 48 in gate where J1 asked 42 in clear. Hinges and latch not listed separately: confirm included.
Gate hinges and latch	latch 1, hinges open	—	—	—	—	—	**Not priced** unless the Vista gate includes them.
Guard posts, PT 4×4 × 8 ft	14	—	—	—	—	—	**Superseded** by Vista aluminium posts on base plates. Blocking under each post is still needed (not counted in J1 either).
Accessories	—	base-plate covers 10 + 4, paint pen 1	Vista via BMR	PB7744/7746/6766	MSRP	210.85	**Priced (MSRP).**
Vista total						**3,851.49**	**Additional to BMR's $8,676.09** (the BMR estimate shows "Vista Rail Package — See separate quote" with no amount). **MSRP, not Brayman's cost. CONFIRM WITH DARCY — Vista payable cost / relationship to BMR estimate.**

Foundation

Requirement	J1 qty	Supplier qty	Supplier	Product	Unit	Extension	Status / explanation
Helical piers / piles	**15**	**11** (10 + 1)	Pro Post	2-3/8 in × 7 ft galvanized, 8 in blade (10) and 10 in blade (1)	295.00 / 315.00	3,265.00	**Variance — see below.**
Pier brackets	15, unless included	included	Pro Post	standard adjustable flat bracket 5 × 5 × 3/16 in	—	0.00	**Priced (included).**
Travel	—	1	Pro Post		85.00	85.00	**Priced.**

Requirement	J1 qty	Supplier qty	Supplier	Product	Unit	Extension	Status / explanation
Engineer report and compliance letter	—	1	Pro Post		400.00	400.00	**Conditional.** Required if the town asks for it with the permit application.
U-brackets	—	—	Pro Post		35.00 each	—	**Optional.**
Pile extensions	—	as needed for torque	Pro Post	2-3/8 in × 7 ft	240.00 each	—	**Conditional.**
Excavation / welder / winter / waiting	—	as needed	Pro Post		105 / 145 / 95 / 95 per hour	—	**Conditional.**

15 piers in J1 against 11 piles from Pro Post

• **J1 (1 Oct 2026):** 15 piers from Brayman's own CT-1 layout: 9 under the upper deck (front beam with piers 6 ft apart, a 12 ft main beam 13 ft out, two wing piers) and 6 under the lower deck. The J1 sheets say the pier product, capacity and beam spans were not checked or certified.

• **Pro Post (6 Oct 2026):** 11 piles "based on our engineer's recommendation", marked on Brayman's A-01 general arrangement plan (29 Sep 2026, the same deck: 18 ft wide, 5 ft clear at centre, 10 ft stairs, 10 × 3 ft lower deck). 7 under the upper deck: two at the pool-side corners, two on a short beam near the pool, three along the front edge (corners and centre; the centre pile is marked in a different colour — the quotation does not say which pile takes the 10 in blade). 4 under the lower deck, one at each corner.

• **Same deck, different framing.** The deck outline matches. The beam arrangement does not: Pro Post's front beam has 3 piles about 9 ft apart where J1 has 4 piers 6 ft apart, and Pro Post has no 12 ft main beam 13 ft out. The lower deck is carried on 4 piles where J1 has 6.

• **The BMR post count fits neither layout exactly.** By J1's cutting rules, 15 posts need 11 sticks and Pro Post's 11 posts need 8; BMR quotes 7. Confirm with Darcy once the foundation is chosen.

FOUNDATION QUANTITY CONFIRMATION REQUIRED — J1 = 15; Pro Post engineered quotation = 11.

The 11-pile quotation is the only written, engineer-based foundation price in the case, and it is used for the current cost. Before construction, Joel and Ben choose one of two things:

1. **Adopt Pro Post's 11 piles** and re-draw the J1 framing to Pro Post's beam lines. The 9 ft front-beam spans and the lower-deck spans must be accepted by Pro Post's engineer or the town's span table, and the BMR beam, post and connector list confirmed against that framing.

2. **Keep J1's 15 piers** and ask Pro Post for a revised quotation. No price for 15 is calculated here.

The earlier working figure of **$350 per helical pier** (Joel, before any written quotation) is **superseded** by OT-2236. It is not used. It was never written into the case.

Other

Requirement	J1	Supplier	Status / explanation
Delivery to 12 D'Arcy's Way	not priced	BMR: "Delivery extra"	**Not priced.**
Carrying	—	BMR: "Carrying extra"	**Not priced.**
Vista delivery	—	not stated	**Not priced.** Confirm with Darcy whether it ships with the BMR order.
Town permit fees	excluded in the J1 customer estimate	—	**Not priced.** Decision: in Linda's price or excluded.
Equipment (Brayman)	none listed	—	**Not priced.** Pro Post brings its own machine.

Requirement	J1	Supplier	Status / explanation
Disposal	not priced	—	**Not priced.**
Brayman labour	no hours on file	—	**Not supplier pricing.** See the internal cost sheet.

Is written supplier pricing now complete?

Nearly, not fully. The three documents give written prices for every principal purchased part: framing lumber and hardware, Trex decking and fascia (BMR); railing and gate (Vista); helical piles with brackets (Pro Post). What still has no usable written price:

1. **Vista's payable price.** The $3,851.49 is MSRP. Brayman's BMR price for it is not written anywhere.
2. **Delivery and carrying** (BMR says extra), and Vista delivery.
3. **Lower-deck skirt** (5 × PT 1×6 × 8 ft): not on the BMR estimate.
4. **Gate hinges and latch**, unless the Vista gate includes them.
5. **Pro Post's price for the final pile count**, if J1's 15 is kept; and OT-2236's validity has lapsed.

The BMR quantities also differ from J1 in several places (stringers, upper joist stock, header stock, post count, hangers). Darcy's estimate says the customer verifies quantities and prices may vary with the final design; those lines are confirmed before ordering.

BMR's prices are held only if the award is confirmed **by 28 Oct 2026**.