

Linda Bushel — preliminary customer estimate — issue J1

Date: 2026-10-01

PRELIMINARY / BUDGET ESTIMATE

Subject to permit review and field verification.

Selling price: NOT ISSUED.

A supplier quotation is not in the case. This sheet does not state a dollar figure. The earlier 1 Oct customer sheet stays as the record from before these layout decisions.

Project

Linda Bushel. Freestanding pressure-treated deck and stairs at an above-ground pool.

12 D'Arcy's Way, Kemptville, ON K0G 1J0.

Drawing: drawings/2026-10-01-j1-preliminary-11x17.pdf.

That set is a preliminary construction and supplier pricing basis. It is not a final construction drawing, not an engineering approval, not a municipal approval, and not a structural certification.

Scope

- Above-ground pool about 21 ft in diameter and about 50 in high. Field verify.
- Upper deck 18 ft wide. Pool edge curved and left open. Other three edges straight. 5 ft clear at the centreline.
- Option A framing: one straight main beam and two wing beams.
- 15 helical piers at the drawn locations. No sonotubes and no concrete. Shaft, helix, length, and capacity are not specified.
- 16 joist lines. 2×8 joists. Segmented curved header.
- Stairs 10 ft wide, about 38 in between surfaces, five risers about 7.6 in, four treads about 11 in. The upper deck is the top landing.
- 10 stair stringers. Each tread is two 5/4×6 boards.
- Working stringer throat 5.00 in. That figure is a design basis for this preliminary package. It is not an engineering certification.
- Lower deck 10 ft by 3 ft. Intended finished walking surface 12 in above grade.
- Guard: the named 37 in Veranda rail kit. Gate 42 in clear, outward swinging, self-closing and self-latching.
- 1×6 skirt on the lower deck only, installed tight.
- Freestanding. No structural attachment to the pool.

Assumptions

- Brown pressure-treated lumber.
- Joist spacing is 16 in on centre maximum, with a 4 in closing space at each upper rim.
- Stringer spacing uses the same 4 in edge spaces. Ten stringers.
- Waste is the offcut from the stated stock lengths. No extra percentage is added.
- Lower 6×6 posts are ordered uncut. The post cut length is reconciled to the field before construction. The dressed beam, joist, and deck stack is 17.5 in.
- Pool-enclosure compliance, including the 1.2 m rule, remains subject to field and municipal verification. The 37 in kit is not redrawn to another height.

Exclusions

- Engineering seal and structural certification.
- Municipal permit approval and permit fees.
- Attachment to the pool.



- A centre stair handrail.
- A guard along the curved pool edge.
- Upper-deck skirting.
- A selling price, deposit, or start date.

Field verification

Pool size and height, finished grades, setbacks, property limits, helical pier product, depth, torque, and bearing, stair rise and run after both deck surfaces are measured, lower-deck post cut length, and pool-enclosure height.

Supplier confirmation

The BMR Winchester request is ready to send. It has not been sent from this record, and no quotation has been returned. The helical pier product, bracket, rail-kit match, gate hinge count, connector brands, bolt diameter, availability, substitution, and delivery timing stay open. Those items are confirmed by the supplier. They are not filled in on this estimate.