

Linda Bushel — internal cost for Ben — issue J1

Date: 2026-10-01

INTERNAL / FOR BEN

Not a customer document. Not sent. No dollar on this sheet is a supplier price. A blank is not zero.

Quantities are issue J1. Joel's 1 Oct 2026 decisions are the geometry: 15 piers, 16 joist lines, 10 stringers, 5.00 in working throat, 12 in lower-deck walking surface, street number 12. The client has selected helical piers. Sonotubes and concrete are not in this issue.

The 29 Sep sheet costing/2026-09-29-ben-internal-cost.md and estimates/internal/2026-10-01-ben-internal-cost.md stay as earlier records. Those earlier sheets still show the unresolved P1 counts.

No labour hours, equipment list, or Darcy quotation is in the case. None was invented.

Material

Item	J1 quantity	Material cost
Helical pier	15	PRICE REQUIRED
Helical-pier bracket, unless included	15	PRICE REQUIRED
PT 6×6 × 8 ft	11	PRICE REQUIRED
Post-to-beam connector	15	PRICE REQUIRED
PT 2×10 × 10 ft	4	PRICE REQUIRED
PT 2×10 × 12 ft	7	PRICE REQUIRED
PT 2×8 × 12 ft	20	PRICE REQUIRED
PT 2×12 × 8 ft stringer stock	10	PRICE REQUIRED
PT 5/4×6 × 20 ft	11	PRICE REQUIRED
PT 5/4×6 × 10 ft	17	PRICE REQUIRED
PT 5/4×6 × 8 ft	7	PRICE REQUIRED
PT 1×6 × 8 ft skirt	5	PRICE REQUIRED
Veranda 37 in × 6 ft appearance	10 straight kits	PRICE REQUIRED
Custom sloped stair guards	2	PRICE REQUIRED
PT 4×4 × 8 ft guard posts	14	PRICE REQUIRED
Gate, 42 in clear	1	PRICE REQUIRED
Gate hinges and latch	Latch 1. Hinge count not issued	PRICE REQUIRED
Stitch bolts / nuts / washers	76 / 76 / 152	PRICE REQUIRED
Header connectors	16	PRICE REQUIRED
Stringer connectors	10	PRICE REQUIRED
Structural screws	100	PRICE REQUIRED
Deck screws	798	PRICE REQUIRED

Material total: NOT CALCULATED.

The Veranda Home Depot identity is not a confirmed BMR SKU. Bolt diameter, saddle model, and connector brand are not specified.

Labour

PRICE REQUIRED. No governed hour allowance is on file for this deck. No dollar rate was applied.

Equipment

PRICE REQUIRED. No equipment list or rate is on file.

Other direct cost

PRICE REQUIRED. Permit fees, disposal, and delivery are not priced. Delivery address for the request is 12 D'Arcy's Way, Kemptville, ON K0G 1J0.

Allowances

The 76 stitch bolts are a pricing allowance, not an engineered schedule. They are not priced.

No percentage waste allowance was added. Offcut waste is the unused length on the J1 cut lists. Offcuts were not deducted from the purchase count. There is no concrete quantity. Helical pier length is not specified.

Direct cost

NOT CALCULATED. Material, labour, equipment, other direct cost, and allowances are not all priced.

Selling price / gross margin

NOT CALCULATED. This sheet does not carry a customer price or a margin. Selling price stays unissued until Darcy's quotation is in the case.