BRAYMAN CONSTRUCTION INC.
411 St. John Street, Merrickville, ON K0G 1N0
CONFIDENTIAL - INTERNAL ONLY

INTERNAL DETAILED COST BREAKDOWN

INTERNAL ONLY

Client	Linda Bushel	**Project**	Bushel Rear Deck (pool deck)
Site	12 D'Arcy's Way, Kemptville, ON K0G 1J0	**Date**	2026-10-27

Material / Package	Direct Cost	Status
Framing lumber — BMR estimate 237147/1	$1,361.71	Written quote; Darcy's price is Brayman's cost. EXPIRES 28 OCT 2026 — confirm/order promptly
Structural hardware — BMR	$389.35	Written quote
Trex Select Island Mist decking — BMR	$4,827.20	Written quote
Trex Island Mist fascia — BMR	$1,666.80	Written quote
Trex fasteners and fascia screw kit — BMR	$431.03	Written quote
Vista 42 in railing and gate — quote 87915-165209	$3,851.49	Written quote, ADDITIONAL to BMR (Joel confirmed). Quoted price is Brayman's cost
Helical piles, 11 — Pro Post OT-2236, SUPPLY AND INSTALL	$3,265.00	Written quote; installation included, so no Brayman pile labour. 11 piles govern; J1 15-pier evidence kept. QUOTE EXPIRED 21 OCT — reconfirm before commitment
Pro Post travel fee	$85.00	Written quote
Pro Post engineer report and compliance letter	$400.00	Written quote. Included as quoted; required if the town asks
Delivery and carrying — BMR	$0.00	BMR: extra; no amount on any document. Absorbed
Equipment	$0.00	None: Pro Post brings its own machine
Town permit fee	Excluded	Not in the customer price; billed at cost
Total materials and subcontract	$16,277.58	BMR $8,676.09 + Vista $3,851.49 + Pro Post $3,750.00

Labour by Task

Task	Hours	Direct Cost
Layout and mark the pile locations	4	$300.00
Posts and beams	16	$1,200.00
Upper-deck framing	24	$1,800.00
Lower-deck framing	8	$600.00
Stairs	16	$1,200.00
Trex decking	16	$1,200.00
Stair treads and risers (Trex)	8	$600.00

Task	Hours	Direct Cost
Trex fascia	5	$375.00
Railing blocking	4	$300.00
Vista railing and gate	16	$1,200.00
Unload and carry materials	4	$300.00
Clean-up and final walk-through	4	$300.00
Total Brayman labour at $75.00 per man-hour	125	$9,375.00

Pricing Reconciliation

Component	Amount
Materials and subcontract	$16,277.58
Brayman labour (125 man-hours × $75.00)	$9,375.00
Total direct cost	$25,652.58
Pricing method	True gross margin 15% (not markup): selling price = direct cost ÷ 0.85
Gross profit	$4,526.93
Selling price before HST	$30,179.51
HST 13%	$3,923.34
Total including HST	$34,102.85
Resulting true gross margin	15.00%
Quote status	BMR/Darcy pricing expires 28 Oct 2026 — confirm/order promptly. Pro Post OT-2236 expired 21 Oct — reconfirm before commitment
Status	For Ben's review. Customer estimate not sent to Linda

Direct costs, labour hours, supplier values, and quoted totals are project-specific and are not stored in this reusable master.